

## SCOPE OF WORK

1. Name of work - Replacement of old fibre sheet and installation of new PPGL sheets (precoated) for assembly area and pathway shelter of TAPPS Kaluchak.

Details are as under :-

<b>S No</b>	<b>Specifications</b>	
(a)	The roof shall be done with PPGL (pre painted galvalume steel) sheet of 0.5MM thickness ISI mark like Tata, Sail/ Jindal/ Essar/Kamdhenu etc. PPLG sheet width 1 meter wide and length as per structure. PPLGL sheet laid over a frame work of trusses and purlin fixed using best quality fasteners with bitumen washer/cup washer. PPLG ridge cover matching colour of width 600mm x 0.5mm thick made from PPGL sheet is to be fixed on top junction of the roof using fasteners. Total area = 6000 sft.	