

FOR UPLOADING ON SCHOOL WEBSITE

DETAILED TENDER NOTICE

1. APS Kaluchak invites tenders from reputed vendors/Agencies/Firms having GST NO for theFollowing Job work :-

SNo	Details	Time Limit in tender
(a)	a) All weather Exterior Emulsion (OBD) Oil bound distempering (two coats) outside the school buildings (including material and painter/labour cost). (b) Putty Work (c) Re-plastering Work (Minor) (d) Fixing of Chips up to height of 3 ft.	Detailed specification as per Appendix "A" .

2. The complete bidding process will be Offline. All the notifications regarding this tender notice will hereafter be published on the school website www.apskaluchak.edu.in.

3. Bidding documents including details of required technical specification can be seen and downloaded from the school website www.apskaluchak.edu.in.

4. Tender documents can be submitted by registered post at the School's address or could be physically dropped in the Quotation Box placed at Tiger Arty Brigade Main Gate Kunjwani Chowk, Jammu (Pin-180010) latest by 1000 hrs **on 29 Sep 2023**. Quotation / Bid will be opened at Conference hall Tiger Arty Bde on **29 Sep 2023 at 1100 hrs** under surveillance of CCTV camera.

5. Technical Bids & Commercial bids will be submitted in separate sealed envelopes with heading pertaining to the type of bid (i.e. whether technical or commercial to be clearly specified on the top of the envelope).

5. The Commercial bids in respect of only those bidders will be considered whose Technical bid meets the required specifications/criteria. Rates applicable should **be valid for a period up to next 60 days** from the date of opening of the tender documents.

6. Liquidated Damage (LD) charges @ 0.5% of the total Contract value shall be weekly levied if work is not completed within the period mentioned in supply order. All rates to be provided including GST.

7. A Demand Draft equivalent to 2% of the value of the quoted cost/amount should also be enclosed as the EMD (refundable) amount alongwith each commercial bid.

SCOPE OF WORK AND TECHNICAL SPECIFICATION

SNO	Scope of work	Technical Specification	Area	Rate per Sq ft
1	All weather Exterior Emulsion (OBD) Oil bound distempering (two coats) outside the school buildings (including material and painter/labour cost).	Previous coating (if cracked or flaked) should be scrapped off completely by washing and scrubbing. If the affected patches are large with deteriorated plaster condition, re-plastering has to be done. The small holes are also required to be filled with Putty/POP. The colour of distemper to be as selected by the School.	84,008 Sq ft	
2	Putty Work	The old surface has to be scrapped completely; any unevenness shall be made good by applying putty/POP on the entire surface including filling up the undulation and the sand papering of the same, after it is dry.	19,805 Sq ft	
3	Re-plastering Work (Minor)	If the affected patches are large with deteriorated plaster condition, re-plastering to be done. The small holes be filled with Putty/POP.	18,561 Sq ft	
4	Fixing of Chips up to height of 3 ft.	Existing structure of plaster be removed/ completely scrapped. Fresh plastering be done and after that chips be fixed. The colour and design of the chips to be as per choice of the School.	7,960 Sq ft	