

FOR QUOTATION

1. APS Kaluchak invites quotation from reputed vendors/agencies/firms having GST No for the item mentioned below: -

S No	Detail	Specification
(a)	Modification Of Girls Changing Room & Washroom (as per spec att)	Detailed specification as per List att

2. The complete bidding process will be offline. All the notifications regarding this tender notice will hereafter be published on the school website www.apskaluchak.edu.in (under **NOTICE BOARD**). Tender documents including details of required technical specifications can be seen and downloaded from the school website www.apskaluchak.edu.in (for further queries please contact mobile No 9086019935 between 0800 hours to 1500 hours)

3. Tender documents can be submitted by registered post at the School's address or could be physically dropped in the Tender Drop Boxes No 02 (01 for Technical Bid and 01 for Commercial Bid) placed at APS Kaluchak Entrance Gate Adjacent to Pari Mahal (Banquet Hall) Jammu, PIN - 180010 (J&K) before 14 Feb 2026.

4. Technical Bid & Commercial Bid is required to be submitted in separate sealed envelopes with heading pertaining to the type of bid (i.e. whether technical or commercial to be clearly specified on the top of the envelope with **nomenclature of the project/work**).

5. The Commercial Bid in respect of only those bidders will be considered whose Technical Bid meets the required specifications/criteria. Rates applicable should be valid for a period up to next 75 days from the date of opening of the tender documents.

6. All vendors are requested to make necessary entry in the register which is kept with security staff at Gate No 1 while dropping bids in the tender boxes.

7. Only printed copy of the Tech Specification provided by the School (in school website) will be accepted duly signed and stamped by the firm/vendor. Any other Tech Specification apart from the one provided by the school in school website will not be accepted.

8. Vendors will only quote the cost of the project in the Commercial bid. Any Tech specification mentioned in Commercial bid will be rejected.

9. Bids must include in terms and conditions for the warranty and post warranty period for undertaking of the AMC .

10. The cost of bids in Commercial bids should include GST or other taxes if any.

11. Only reputed brands will be accepted. No Chinese/assembled products will be accepted.

12. The School Reserves the right to cancel the project at any stage.

13. Vendor's own specification will not be accepted.

Sd/xxxxx
Principal

**TECHNICAL SPECIFICATION OF MODIFICATION OF GIRLS CHANGING ROOM
& WASHROOM**

S NO	DESCRIPTION OF ITEM	DIMENSION	QTY
	<p><u>Construction of New Convenience room for girls students</u></p> <ul style="list-style-type: none"> ● Bathroom cum changing room ● Girls Toilet ● Height of wall ● Brick partition wall, cement plastering & painting work, Wall / floor tiling work. ● Aluminum doors and ventilation, electrical work and sanitary fitting/ drainage system/water pipe line etc. as per specification or scope of work mention as below. 	<p>7' x 3' 9" 3' x 4' 3" 7"</p>	<p>03 Nos 03 Nos</p>
	<ol style="list-style-type: none"> 1. Dismantling of Brick work 2. Dismantling of Concrete Flooring 3. Dismantling of existing RCC slab 4. Taking Out of old doors & Floors 	<p>150 cft 180 cft 135 cft</p>	<p>04 Nos</p>
	<ol style="list-style-type: none"> 5. Earth work of foundation and re-filling of excavation of earth etc. 6. Construction of Half Brick work 1:4 cement mortar 7. 12 mm cement plaster of mix: 1:6 (1 cement: 6 fine sand) 8. Laying of cement concrete for levelling of plinth level: 1:3:6 9. Laying of New RCC plinth beam and lintel beam 1:1.5:3 10. Cantering and shuttering of New plinth & lintel beam etc. 11. Steel reinforcement for New R.C.C. work 12. Distempering with oil bound distemper of ceiling & wall up to two washrooms. including priming coat 	<p>1200 Cft 450 Sq. ft 1200 sq.ft. 410 cft 140 Cft 210 Sq.ft. 105 kg 1200 Sq. ft</p>	
	<ol style="list-style-type: none"> 13. Supply & fixing of Vitrified tiles in floor in different sizes floor tiles of size 600 x 600 of approved make 14. Supply & fixing of 1st quality ceramic glazed wall tiles of approved make (up to 7 feet) 15. PVC heavy duty drain pipe pitting for toilet seat, wash basin, and urinal system complete work: 110 & 75 mm bore pipe 16. Fixing (CPVC) pipes, water supply including all CPVC plain & brass threaded fittings and complete work: 15 and 20 mm 17. Fixing square-mouth S.W. gully trap class SP-1 complete brick masonry chamber. 18. P/L cement concrete (1:5:10) up to haunches of 110 mm & 75 mm PVC drain pipe 	<p>350 sq ft 1050 sq ft 250 Rft 400 Rft</p>	<p>03 Nos 250 Rft</p>

<p>19. S/F aluminum doors, windows, ventilators with extruded built up standard tubular sections and other sections of approved make, all complete open able door frame & shutter etc. (size of door 7x2.5 feet) Ventilation 2 x1 feet</p> <p>20. Fixing ACP sheet 3mm thick in aluminum door, shutters with EPDM rubber / neoprene gasket etc</p> <p>21. S/ F aluminum sliding door bolts, size 300x 16mm, ISI marked</p> <p>22. S/F aluminum tower bolts, size 200x10mm, ISI marked</p> <p>23. S/F aluminum handles, size 150 mm ISI marked</p> <p>24. S/F aluminum die cast body tubular type universal hydraulic door closer.</p>		<p>Door-06 Nos</p> <p>Ventilation – 06 Nos</p>
<p>25. S/F white Vitreous china s china pedestal type water closet (European type W.C. pan) complete all fitting.</p> <p>26. S/F 10 liter low level white P.V.C. flushing cistern, including flush pipe, with manually controlled.</p> <p>27. S/F white Vitreous China Wash basin size 550x400 mm with pedestal complete fitting.</p> <p>28. S/F CP Bib tap/ pillar cock/ angle valve (fancy type) 15 mm</p> <p>29. S/F CP Concealed stop cock extra heavy body with adjustable wall flange</p> <p>30. S/F CP soap dish/ shop container</p> <p>31. S/F CP towel ring complete with all respect</p> <p>32. S/F CP Grating Doom 100 mm dia, fixed in floor</p> <p>33. S/F good quality of Glass mirror 600x450 mm</p> <p>34. S/F CP jet complete fitting</p> <p>35. S/F CP cup complete fitting</p> <p>36. Constructing brick masonry manhole in cement mortar 1:4 (1cement : 4 coarse sand) with R.C.C. top slab</p> <p>37. Supply and fixing 1000 lit cap. PVC water tank and steel structure frame work up to 15 feet complete fitting.</p>		<p>03 Nos</p> <p>03 Nos</p> <p>02 Nos</p> <p>09 Nos</p> <p>06 Nos</p> <p>02 Nos</p> <p>05 Nos</p> <p>06 Nos</p> <p>02 Nos</p> <p>03 Nos</p> <p>14 Nos</p> <p>01 Nos</p> <p>01 Nos</p>
<p>38. Wiring for light point/ exhaust fan point with 1.5 sq.mm FR PVC insulated copper conductor single core cable</p> <p>39. S/F PVC insulated copper conductor, single core 2 x 1.5 sq.mm + 1 x 1.5 sq. mm earth wire</p> <p>40. S/F PVC conduit along with accessories in surface/recess 20 mm dia</p> <p>41. Metal box of following sizes (nominal size) on surface 100 mm X 150 mm X 60 mm deep</p> <p>42. Switch & socket 5/15 Amp compatible</p> <p>43. 4 feet LED type light 20 W-230V, with complete fitting</p> <p>44. Exhaust fan heavy duty 250 mm sweep with louvers</p> <p>Note : All Sanitary fitting should be of Cera/Hindware; All Electrical items & PVC items should be of repudiated brand.]</p>	<p>400 Rft</p> <p>200 Rft</p>	<p>08 Nos</p> <p>02 Nos</p> <p>12 Nos</p> <p>06 Nos</p> <p>02 Nos</p>

TECHNICAL BID

To
The Principal
Army Public School
Kaluchak

DATE :- _____

GST NO _____

S NO	DESCRIPTION OF ITEM	DIMENSION	QTY
	<p><u>Construction of New Convenience room for girls students</u></p> <ul style="list-style-type: none"> ● Bathroom cum changing room ● Girls Toilet ● Height of wall ● Brick partition wall, cement plastering & painting work, Wall / floor tiling work. ● Aluminum doors and ventilation, electrical work and sanitary fitting/ drainage system/water pipe line etc. as per specification or scope of work mention as below. 	<p>7' x 3' 9" 3' x 4' 3" 7 feet</p>	<p>03 Nos 03 Nos</p>
	<ol style="list-style-type: none"> 1. Dismantling of Brick work 2. Dismantling of Concrete Flooring 3. Dismantling of existing RCC slab 4. Taking Out of old doors & Floors 	<p>150 cft 180 cft 135 cft</p>	<p>04 Nos</p>
	<ol style="list-style-type: none"> 5. Earth work of foundation and re-filling of excavation of earth etc. 6. Construction of Half Brick work 1:4 cement mortar 7. 12 mm cement plaster of mix: 1:6 (1 cement: 6 fine sand) 8. Laying of cement concrete for levelling of plinth level: 1:3:6 9. Laying of New RCC plinth beam and lintel beam 1:1.5:3 10. Cantering and shuttering of New plinth & lintel beam etc. 11. Steel reinforcement for New R.C.C. work 12. Distempering with oil bound distemper of ceiling & wall up to two washrooms. including priming coat 	<p>1200 Cft 450 Sq. ft 1200 sq.ft. 410 cft 140 Cft 210 Sq.ft. 105 kg 1200 Sq. ft</p>	
	<ol style="list-style-type: none"> 13. Supply & fixing of Vitrified tiles in floor in different sizes floor tiles of size 600 x 600 of approved make 14. Supply & fixing of 1st quality ceramic glazed wall tiles of approved make (up to 7 feet) 15. PVC heavy duty drain pipe pitting for toilet seat, wash basin, and urinal system complete work: 110 & 75 mm bore pipe 16. Fixing (CPVC) pipes, water supply including all CPVC plain & brass threaded fittings and complete work: 15 and 20 mm 17. Fixing square-mouth S.W. gully trap class SP-1 complete brick masonry chamber. 18. P/L cement concrete (1:5:10) up to haunches of 110 mm & 75 mm PVC drain pipe 	<p>350 sq ft 1050 sq ft 250 Rft 400 Rft</p>	<p>03 Nos 250 Rft</p>

	<p>19. S/F aluminum doors, windows, ventilators with extruded built up standard tubular sections and other sections of approved make, all complete open able door frame & shutter etc. (size of door 7x2.5 feet) Ventilation 2 x1 feet</p> <p>20. Fixing ACP sheet 3mm thick in aluminum door, shutters with EPDM rubber / neoprene gasket etc</p> <p>21. S/ F aluminum sliding door bolts, size 300x 16mm, ISI marked</p> <p>22. S/F aluminum tower bolts, size 200x10mm, ISI marked</p> <p>23. S/F aluminum handles, size 150 mm ISI marked</p> <p>24. S/F aluminum die cast body tubular type universal hydraulic door closer.</p>		<p>Door-06 Nos</p> <p>Ventilation – 06 Nos</p>
	<p>25. S/F white Vitreous china s china pedestal type water closet (European type W.C. pan) complete all fitting.</p> <p>26. S/F 10 liter low level white P.V.C. flushing cistern, including flush pipe, with manually controlled.</p> <p>27. S/F white Vitreous China Wash basin size 550x400 mm with pedestal complete fitting.</p> <p>28. S/F CP Bib tap/ pillar cock/ angle valve (fancy type) 15 mm</p> <p>29. S/F CP Concealed stop cock extra heavy body with adjustable wall flange</p> <p>30. S/F CP soap dish/ shop container</p> <p>31. S/F CP towel ring complete with all respect</p> <p>32. S/F CP Grating Doom 100 mm dia, fixed in floor</p> <p>33. S/F good quality of Glass mirror 600x450 mm</p> <p>34. S/F CP jet complete fitting</p> <p>35. S/F CP cup complete fitting</p> <p>36. Constructing brick masonry manhole in cement mortar 1:4 (1cement : 4 coarse sand) with R.C.C. top slab</p> <p>37. Supply and fixing 1000 lit cap. PVC water tank and steel structure frame work up to 15 feet complete fitting.</p>		<p>03 Nos</p> <p>03 Nos</p> <p>02 Nos</p> <p>09 Nos</p> <p>06 Nos</p> <p>02 Nos</p> <p>05 Nos</p> <p>06 Nos</p> <p>02 Nos</p> <p>03 Nos</p> <p>14 Nos</p> <p>01 Nos</p> <p>01 Nos</p>
	<p>38. Wiring for light point/ exhaust fan point with 1.5 sq.mm FR PVC insulated copper conductor single core cable</p> <p>39. S/F PVC insulated copper conductor, single core 2 x 1.5 sq.mm + 1 x 1.5 sq. mm earth wire</p> <p>40. S/F PVC conduit along with accessories in surface/recess 20 mm dia</p> <p>41. Metal box of following sizes (nominal size) on surface 100 mm X 150 mm X 60 mm deep</p> <p>42. Switch & socket 5/15 Amp compatible</p> <p>43. 4 feet LED type light 20 W-230V, with complete fitting</p> <p>44. Exhaust fan heavy duty 250 mm sweep with louvers</p> <p>[Note : All Sanitary fitting should be of Cera/Hindware; All Electrical items & PVC items should be of repudiated brand.]</p>	<p>400 Rft</p> <p>200 Rft</p>	<p>08 Nos</p> <p>02 Nos</p> <p>12 Nos</p> <p>06 Nos</p> <p>02 Nos</p>

QUOTATIONS FOR MODIFICATION OF GIRLS CHANGING ROOM & WASHROOM

Signature with Stamp

COMMERCIAL BID

To
The Principal
Army Public School
Kaluchak

DATE :- _____

GST NO _____

QUOTATIONS FOR MODIFICATION OF GIRLS CHANGING ROOM & WASHROOM

S No	ITEMS/PROJECT	QTY	AMOUNT
(a)	Modification Of Girls Changing Room & Washroom (as per specification att)	03 each	
Total			
GST			
Total Amount included GST			

Signature with Stamp